



01/04/2024

Dear Sir:

We would like to certify that the 2S Concrete Sand from the Hall Pit # FA122 does confirm to the NCDOT specifications and is approved to use in NCDOT projects. We sampled material from this location on 01/03/2024 and it conformed to both NCDOT and ASTM-33 specifications.

Sincerely,

A handwritten signature in black ink, appearing to read 'Karen Newport'.

Karen Newport
CEO

| | |
|-------------|------------|
| Date: | 1/3/2024 |
| Sample # | 4 |
| Qty Testing | 2000 |
| Plant | Hall FA122 |

| Sieve Size | Cumulative gms Retained | Cumulative % Retained | Percent Passing | NCDOT Specs. (% Passing) |
|----------------------------|-------------------------|-----------------------|-----------------|--------------------------|
| 3/8 " | 0 | 0 | 100 | |
| #4 | 2.2 | 0 | 100 | 95 - 100 |
| #8 | 15.1 | 3 | 97 | 80 - 100 |
| #16 | 99.6 | 20 | 80 | 45 - 95 |
| #30 | 293.9 | 60 | 40 | 25 - 75 |
| #50 | 442.7 | 90 | 10 | 5 - 30 |
| #100 | 478.5 | 97 | 3 | 0 - 10 |
| Pan | 492.8 | | | |
| Passing #200 (wash method) | | | | |
| #200 | 483 | | 1.8 | 0 - 3 |

| | |
|---------------------------------|-------|
| Total Dry Weight. (before wash) | 492.8 |
| Wt. After Washing. | 483.9 |

| | |
|----|------|
| FM | 2.70 |
|----|------|

| | |
|------------|-------|
| Wet Wt | 527.6 |
| Moisture % | 7 |